

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20552-00-00
Spot: S2SESW Sec/Twnshp/Rge: 17-21S-1W
330 feet from S Section Line, 2040 feet from W Section Line
Lease Name: CHAVEZ Well #: 2
County: MCPHERSON Total Vertical Depth: 2960 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2960		85 SX
SURF	8.625	156		125 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/14/2012 10:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: DOUGLAS D. LOEWEN Company: _____ Phone: (620) 628-4425

Proposed Plugging Method: AS PER KCC DISTRICT #2 RULES & REGS

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 05/15/2012 1:30 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

5/14/2012, RAN BAILER DOWN TO 2960' DUMPED SAND AND A 4 SX CAP. HIT PLUG AT 2870'. SHOT CASING AT 400' 4 SHOTS FROM 400 TO 401', RAN TUBING DOWN TO 400' CIRCULATED WATER THEN PUMPED 265 SX OF 60/40 4% TO SURFACE. 5/15/2012 CEMENT DROPPED TO 600' IN 4.5" AND TO A DEPTH OF 400' ON THE BACKSIDE. PUMPED 47 SX OF 60/40 4% IN THE 4.5" AND 150 SX OF 60/40 4% THE FILL THE SURFACE PIPE TO THE TOP.

Perfs:

Top	Bot	Thru	Comments
2949	2958		MISSISSIPPIAN
2929	2944		MISSISSIPPIAN

RECEIVED
OCT 22 2012
KCC WICHITA

Remarks: COPLAND CEMENT TICKET #37916. PLUGGED PER COMMISSION ORDER FAILURE TO TA

Plugged through: TBG

District: 02

Signed [Signature] (TECHNICIAN)
10/23/12