

1 030662

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,353-0000

SW NE NE, SEC. 19, T 16 S, R 18 W/4  
4290 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Haas "A" Well # 1

Operator: F & M Oil Co., Inc.  
Name & Address: 422 Union Center  
Wichita, KS 67202

County Rush 117.55  
Well Total Depth 3617 Granite Wash feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Union Drilling Co., Inc. License Number 5103

Address 422 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 21 Month: February Year: 19 86

Plugging proposal received from Lyle Cason

(company name) Union (phone) 316-262-1872

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1197-1227'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:45 am Day: 21 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1259' with 50 sx cement, 2nd plug at 847' with 80 sx cement, 3rd plug at 366' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement.

STATE CORPORATION COMMISSION

MAR 4 1986

Remarks: Used 60/40 Pozmix 6% gel by Allied.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

(I (X) / did not) observe this plugging.

MAR 0 4 1986

Signed Steve Durrant (TECHNICIAN)

DATE 12843

WELL NO.

2-2 / APR 10 1986

