

1090144

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,948-0000

NW NE NE, SEC. 19, T 17 S, R 28 ~~W~~

330 feet from ~~N~~ section line

990 feet from ~~W~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Fuller Well # 4-19

Operator: Gear Petroleum Co., Inc.

County Lane

Name & Address 300 Sutton Place

Well Total Depth 4600 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 10:00 pm Day: 16 Month: March Year: 19 84

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-653-7716

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2160' with 50 sx cement

2nd plug at 1620' with 50 sx cement

3rd plug at 390' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:15 am Day: 17 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement, 2nd plug at 1620' with

50 sx cement, 3rd plug at 390' with 40 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION
3-21-84
MAR 21 1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied # 32530

(If additional description is necessary, use BACK of this form.)

(xxx) (do not) observe this plugging.

Signed R. Barluttan
(TECHNICIAN)

INVOICED

DATE 3-23-84

INV. NO. 0903