

1060983

6-17-87

Top
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,312 -0000

NE SW SE, SEC. 19, T 17 S, R 28 W/E
990 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Garton Well # 1-19

Operator: Landmark Oil Exploration, Inc.

County Lane 146.74

Name & Address 110 South Main, Suite 510

Well Total Depth 4515 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hembree Well Service License Number 6907

Address 302 East Sycamore, Box 458, Ness City, KS 67560

Company to plug at: Hour: 2 p.m. Day: 17 Month: 6 Year: 19 87

Plugging proposal received from George Harmison

(company name) Hembree Well Service (phone) 913-798-3408

were: 4 1/2" at 4515' Perfs at 4160' Anhydrite 2055'

1st plug sand back to 4110' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 175 sx cement.

Plugging Proposal Received by Richard Lacey & Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 17 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4110' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 175 sx cement.

Maximum pressure 650 psi and shut in 275 psi.

Remarks: Used 60/40 Pozmix by Halliburton. Recovered 2300' 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

6-19-87
JUN 19 1987

INVOICED observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 6-22-87

INV. NO. 17286 6-17

INVOICE

DATE: _____
BY: _____