

10-18

137
R

To: 1070863
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,515 - 0000
SE SW NE, SEC. 21, T 17 S, R 28 W/E
2970 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181
Operator: Donald C. Slawson Oil Producers
Name & Address: 20 N. Broadway, #700
Oklahoma City, OK 73102

Lease Name Borell Well # D-1
County Lane 150.47
Well Total Depth 4630 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 414

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:20 a.m. Day: 18 Month: 10 Year: 19 90

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4629' w/300 sx cement, Perfs at 4201-03'

1st plug sand back to 4150' and dump 4 sx cement on top of sand through bailer,

2nd plug pull casing to 2150' and spot 10 sx gel followed by 50 sx cement through casing,

3rd plug pump 75 sx cement at 1400', 4th plug pump 50 sx cement at 430',

5th plug top off with 10 sx cement at 40'.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 18 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dumped 4 sx cement on top of

sand through bailer,

2nd plug pulled casing to 2150' and spotted 10 sx gel followed by 50 sx cement through

casing, 10-23-90

3rd plug pumped 1400' with 75 sx cement,

4th plug pumped 430' with 50 sx cement, 5th plug topped off with 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED (if applicable) observe this plugging.

Signed Dan Goodrow (TECHNICIAN)

DATE 11-6-90

INV. NO. 29852