

1 070260

NOV 26 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,739-0000

NE SE SE, SEC. 21, T 17 S, R 28 W
990 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Riley Well # 1

Operator: Chief Drilling Co., Inc.

County Lane 149.12

Name & Address 151 N. Main, Suite #700

Well Total Depth 4590 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 26 Month: 11 Year: 19 86

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering (phone) 316-792-2506

were: 4 1/2" at 4481' PBTD 4468' Perfs at 4204-10'

1st plug sand back to 4150' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 70 sx cement, 15 sx gel, 1 sx hulls,

release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 26 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dumped 4 sx cement on top of sand
through bailer.

2nd plug squeezed well with 300 lbs. hulls, 10 sx gel, 70 sx cement, 15 sx gel, 100 lbs.
hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 150 psi.

Recovered 2200' of 4 1/2" casing.

Remarks: Used 60/40 Pozmix 6% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(City/State) observe this plugging.

DATE 12-5-86

Signed Dan Gooden
(TECHNICIAN)

INV. NO. 15499