

1070417

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,416-0000

NE SW NE, SEC. 21, T 17 S, R 28 W/E

3630 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Borell "C" Well # 1-21

Operator: Landmark Oil Exploration, Inc.
Name & Address: 110 South Main, Suite 510
Wichita, KS 67202

County Lane 148.85

Well Total Depth 4580 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Beredco Inc. License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 12 Month: 9 Year: 19 87

Plugging proposal received from Howard Cain

(company name) Beredco Inc. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2761'

1st plug at 2166' with 50 sx cement, 2nd plug at 1300' with 80 sx cement, Anhydrite 2130-66'

3rd plug at 300' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9 p.m. Day: 12 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2166' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. (If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
9-15-87
SEP 15 1987
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
Please observe this plugging.

DATE 9-17-87

Signed Dan Gordon (TECHNICIAN)

INV. NO. 18143
OCT 29 1987