

1 020384

6-8

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,587-~~0000~~

SW SW SW, SEC. 21, T 17 S, R 28 W/E

330 feet from S section line

4950 feet from E section line

Lena Pelton Estate

Lease Name \_\_\_\_\_ Well # 1

County Lane \_\_\_\_\_ 150.31

Well Total Depth \_\_\_\_\_ 4625 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 211

TECHNICIAN'S PLUGGING REPORT

Operator License # 30581

Operator: AGAPEX Limited

Name & Address 4420 West 32nd Ave.

Denver, CO 80212

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Blue Goose Drilling Company, Inc. License Number 5104

Address P.O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 5 p.m. Day: 8 Month: 6 Year: 19 91

Plugging proposal received from Mark Miller

(company name) Blue Goose Drilling Company, Inc. (phone) 316-792-5633

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2175' with 50 sx cement, 2nd plug at 1300' with 50 sx cement,

3rd plug at 700' with 50 sx cement, 4th plug at 211' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 8:45 p.m. Day: 8 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2175' with 50 sx cement,

2nd plug at 1300' with 50 sx cement,

3rd plug at 700' with 50 sx cement,

4th plug at 211' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION

6-17-91  
JUN 17 1991

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

do not observe this plugging.

DATE 6-20-91

INV. NO. 32189

6-8

Signed Glenn R Barlow (TECHNICIAN)