

To: 1 070387
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER ~~15-~~ ^{N/A} K-165-21036-0000
NW NW SE, SEC. ³⁵ 36, T 16 S, R 18 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Operator: Frontier Oil Company
Name & Address: 1720 Kansas State Bank Building
Wichita, KS 67202

2310 feet from S section line

2310 feet from E section line

Lease Name Herrman Well # A-1

County Rush 119.23

Well Total Depth 3684 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1213

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 7 Month: 8 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 3683' Perfs at 2811-60'

1st plug sand back to 2760' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 7 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 2760' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 110 sx cement.

RECEIVED STATE CORPORATION COMMISSION

AUG 12 1987

8-12-87

Maximum pressure 900 psi and shut in 700 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2228' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 8-14-87

Signed Dan Gordon (TECHNICIAN)

INV. NO. 17817