

To: **1 041161**
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 165-21,554-0000

W/2 SW SE, SEC. 36, T 16 S, R 18 W/E
660 feet from S section line
2310 feet from E section line

4-3

TECHNICIAN'S PLUGGING REPORT

Operator License # 30658
Operator: ANR Production
Name & Address: 9 Greenway Plaza, Ste. 2751
Houston, TX 77046

Lease Name Honderick Well # 1
County Rush 122.55
Well Total Depth 3771 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1200

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____
Address _____

Company to plug at: Hour: 9 a.m. Day: 3 Month: 4 Year: 19 96

Plugging proposal received from Jerry Colburn
(company name) ANR Production (phone) 316-697-2137

were: 5 1/2" at 3770' w/435 sx cement, TOC approx. 1100', Perfs at 3600-3714', PBD 3765'
1st plug set CIBP at 3575' with 2 sx cement on top,
2nd plug perforate at 1000' and circulate cement in annulus and fill 5 1/2" casing.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10 a.m. Day: 3 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3575' with 2 sx cement on top,
Loaded hole with water and perforated at 1000',
2nd plug pumped 200 sx cement, circulated through 8 5/8".
Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE APR 18 1996
INV. NO. 45332
4-3

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1996