

1 050788

DB 10/26/11

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,298-~~0000~~
SW SE SE, SEC. 35, T 16 S, R 30 W/E^X
330 feet from S section line
1020 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181
Operator: Donald C. Slawson
Name & Address 200 Douglas Building
Wichita, KS 67202

Lease Name Sharp 'M' Well # 1
County Lane 150.48
Well Total Depth 4630 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657
Address P. O. Box 1409, Great Bend, KS 67530

Company to plug at: Hour: 12:30 pm Day: 26 Month: March Year: 19 86

Plugging proposal received from Jack Richardson
(company name) Slawson (phone) 316-793-3561

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2841'
Anhydrite 2228-58'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement
Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:50 pm Day: 26 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2258' with 50 sx cement, 2nd plug at 1443' with 80 sx
cement, 3rd plug at 362' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15
sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE APR 1 1986
INV. NO. 13216

observe this plugging.
STATE CORPORATION COMMISSION
Signed Richard W. Lacey
(TECHNICIAN)

MAR 31 1986
3-31-86
CONSERVATION DIVISION
Wichita, Kansas