

1 070235

56  
R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,338 -0000  
NW NE SW SEC. 35, T 16 S, R 30 W/E  
2145 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4661/6194

Lease Name J.A.S. Well # 1-35

Operator: Galloway Petroleum Explr, Inc. &  
Name & ESP Development  
Address 300 Broadway Plaza Bldg.  
Wichita, KS 67202

County Lane Lane 149.83

Well Total Depth 4610 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 383

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 KS State Bank Bldg., Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 15 Month: 10 Year: 19 86

Plugging proposal received from Bruce Fickel

(company name) Red Tiger Drilling Company (phone) 913-625-7821

were: To fill with heavy mud and spot cement through drill pipe Elevation 2849' KB-5'  
Anhydrite 2231-2260'

1st plug at 2200' with 50 sx cement, 2nd plug at 1450' with 75 sx cement

3rd plug at 400' with 40 sx cement

4th plug at 40' with 10 sx cement

5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Don Ubel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 8:20 a.m. Day: 15 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2260' with 50 sx cement

2nd plug at 1460' with 100 sx cement

3rd plug at 410' with 50 sx cement

4th plug at 40-0' with 10 sx cement

5th plug to circulate rathole with 10 sx cement

RECEIVED  
STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA, KS

10-16-86  
OCT 16 1986

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
I should ~~XXXXXX~~ observe this plugging.

DATE 10-17-86

Signed Don Ubel  
(TECHNICIAN)

INV. NO. 15187