

To: 1 51344 S-4
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,166 -0000
SE NW NW SE, SEC. 36, T 16 S, R 30 W/E

2220 feet from S section line
2040 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30188
Operator: Royal Petroleum
Name & Address P.O. Box 1815
Liberal, KS 67905-1815

Lease Name Snider Well # 1
County Lane
Well Total Depth 4590 149.17 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1 p.m. Day: 4 Month: 5 Year: 19 93

Plugging proposal received from Bob Sargent
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

work: 5 1/2" at 4588' w/150 sx cement, PBD 4546', Perfs at 4509-10, 4515-19, 4772-76, 4456'
DV tool at 2252' w/500 sx cement,

1st plug pump 300 lbs. hulls and cement to fill.
2nd plug check backside.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 4 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls and 350 sx cement down 5 1/2" casing.
Maximum pressure 500 psi and shut in 200 psi.

2nd plug pumped 25 sx cement down 8 5/8" X 5 1/2" annulus. Maximum pressure 700 psi and shut in 700 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)
Observe this plugging.

INVOICED
DATE 5-17-93
INV. NO. 37216
S-4

Signed Richard M. Lacey
(TECHNICIAN)
RECEIVED
5-10-93
MAY 10 1993
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-2/3
Rev. 01-84