

1 070015

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238
Operator: Petroleum, Inc.
Name & Address 300 W. Douglas, Suite 800
Wichita, KS 67202

API NUMBER 15- 101-21,198 -0000
NE NE SW, SEC. 36, 'T. 16 S, R 30 W/E
2310 feet from S section line
2970 feet from E section line
Lease Name Snider 'C' Well # 1
County _____ Lane 182.49
Well Total Depth 5615 (Mississippi) feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 304
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor DNB Drilling, Inc. License Number 5476
Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 2:30 pm Day: 5 Month: August Year: 19 85

Plugging proposal received from John C. Taylor

(company name) DNB (phone) 316-687-5471

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2241
Elevation 2848 KB

1st plug at 2250' with 50 sx cement

2nd plug at 1200' with 70 sx cement

3rd plug at 720' with 50 sx cement 4th plug at 330' with 40 sx cement
solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rat hole with 10 sx cement
Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 4:30 pm Day: 5 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement, 2nd plug at 1200' with 70 sx
cement, 3rd plug at 720' with 50 sx cement, 4th plug at 330' with 40 sx cement, 5th
& 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,
7th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1985
8-13-85
CONSERVATION DIVISION
Wichita, Kansas

INVOICED (void if crossed out) observe this plugging.

Signed Dan Gordon
(TECHNICIAN)

DATE 8-14-85
INV. NO. 9591

SEP 11 1985 OCT 11 1985