

To: 1 030553
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,229 -0000
100' south
NE SE NW, SEC. 36, T 16 S, R 30 W/E
3530 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Kropp Well # 2-36

Operator: Gear Petroleum Co., Inc.
Name & Address 300 Sutton Place
Wichita, KS 67202

County Lane Lane 151.06
Well Total Depth 4648 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 15 Month: October Year: 19 85

Plugging proposal received from Bruce Fickle

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2843
Anhydrite 2260

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 am Day: 15 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2260' with 50 sx cement, 2nd plug at 1100' with 80 sx
cement, 3rd plug at 375' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10
sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

OCT 28 1985
10-28-85
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
OCT 29 1985

Signed Steve Durrant
(TECHNICIAN)

P. a. S.

DATE

INV. NO. 10777