

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-20381-00-01
Spot: NENE Sec/Twnshp/Rge: 3-16S-20W
667 feet from N Section Line, 621 feet from E Section Line
Lease Name: CROTINGER OWWO Well #: 1
County: RUSH Total Vertical Depth: 3860 feet

Operator License No.: 733636
Op Name: TRIUNITED INVESTORS, LLC
Address: 18598 TWIN CREEKS RD
MONTE SERENO, CA 95030

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3716	0	WITH 150 SX CMT
SURF	8.625	232		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/19/2012 9:30 AM
Plug Co. License No.: 33636 Plug Co. Name: TRIUNITED INVESTORS, LLC
Proposal Rcvd. from: JOHN FOSE Company: TRIUNITED INVESTORS, LLC Phone: (785) 623-0002

Proposed Plugging Method: SAND TO 3425' & 4 SX CMT. PERFORATE @ 1430' & 50 SX CMT. PERFORATE @ 900' & 50 SX CMT. PERFORATE @ 270'. CMT TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/19/2012 1:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFORATED @ 900'. RUN TBG TO 3425' & SPOT 40 SX CMT. PULL TBG TO 900' & PUMP 180 SX CMT. CMT CIRCULATED UP BACKSIDE & CASING BOTH. PULLED TBG & TIED ONTO CASING & PUMPED 10 SX CMT. CMT CIRCULATED OUT BACKSIDE. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
3517	3520		
3491	3494		
3473	3476		

RECEIVED
SEP 27 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Michael J. Main
10/19/12 (TECHNICIAN)

RECEIVED

SEP 20 2012

KCC WICHITA CITY

AMZ