

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-30469-00-00
Spot: W2E2E2SE Sec/Twnshp/Rge: 29-26S-20E
1320 feet from S Section Line, 495 feet from E Section Line
Lease Name: CAMPBELL Well #: 1-7-13
County: ALLEN Total Vertical Depth: 915 feet

Operator License No.: 4485
Op Name: VERDE OIL COMPANY
Address: 1020 NE LOOP 410 STE 555
SAN ANTONIO, TX 78209

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
SURF	7	22		4 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/16/2012 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: JEFFREY L. DALE Company: _____ Phone: (620) 754-3800

Proposed Plugging Method: Spot 20 sack plug at TD (110'). Spot 20 sack plug at 500' (110'). Cement from 225' to surface. All cement will be Class A.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the well to TD. Mixed and pumped 3 sacks of gel down the 1" pipe to TD. Pumped 15 sacks of cement through the 1" pipe at TD. Pulled 1" pipe up to 500'. Pumped 15 sacks of cement through the 1" pipe at 500'. Pulled 1" pipe up to 250'. Circulated 40 sacks of cement through the 1" pipe from 250' to surface. Pulled the rest of the 1" pipe out of the hole and topped the well off with cement. A total of 70 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED

SEP 26 2012

KCC Chanute Dist. #3

RD

RECEIVED

SEP 28 2012


KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed


8/29/12 (TECHNICIAN)