

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-25476-00-00  
Spot: NESWSESW Sec/Twnshp/Rge: 15-17S-25W  
544 feet from S Section Line, 1804 feet from W Section Line  
Lease Name: PATRICIA ANN Well #: 1  
County: NESS Total Vertical Depth: 4540 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	218		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/18/2012 9:20 PM  
Plug Co. License No.: 4958 Plug Co. Name: MALLARD, J. V., INC.  
Proposal Rcvd. from: KATHY Company: MALLARD, J. V., INC. Phone: (620) 241-4640

Proposed Plugging Method: 1ST PLUG AT 1850' WITH 50 SX CMT. 2ND PLUG AT 1130' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE  
Date/Time Plugging Completed: 09/18/2012 11:45 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

1ST PLUG AT 1850' WITH 50 SX CMT. 2ND PLUG AT 1130' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED  
SEP 19 2012  
KCC DOWNEY CITY

Signed

Ken Jehlik  
(TECHNICIAN)