

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21626-00-00
Spot: NWNE Sec/Twnshp/Rge: 30-31S-1W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: WAUGH Well #: 6
County: SUMNER Total Vertical Depth: 3720 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3719		300 SX
SURF	8.625	460		250 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 05/19/2011 12:00 AM
Plug Co. License No.: 34231 Plug Co. Name: M & S WELL SERVICE, LLC
Proposal Revd. from: THAD STARR Company: AMERICAN ENERGY Phone: (620) 793-2146

Proposed Plugging Method: SAND BACK TO AND CAP WITH 4SKS OF CEMENT. PERFORATE THE CASING AT 510' AND CIRC CERMENT TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 05/19/2011 9:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3575' AND CAPPED WITH 4 SKS OF CEMENT. NO RECOVERY. THE CASING WAS PERFORATED AT 510' AND CEMENT WAS CIRCULATED TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3655	3666	CSG	

Remarks: CONSOLIDATED CEMENTING 60/40 4% GEL CACL DENIED TA

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

RECEIVED
OCT 05 2012
KCC WICHITA