

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21562-00-00
Spot: SESWNE Sec/Twnshp/Rge: 30-31S-1W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: WAUGH Well #: 3
County: SUMNER Total Vertical Depth: 3740 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3736		125 sxs
SURF	8.625	453		265 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2011 12:00 AM
Plug Co. License No.: 34231 Plug Co. Name: M & S WELL SERVICE, LLC
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGY Phone: (620) 793-2146

Proposed Plugging Method: SAND BACK PERFS TO 3580' AND CAP WITH 4 SKS OF CEMENT. 35 SKS 503' CIRC CEMENT 250'-0'.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 05/19/2011 11:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3550' AND CAPPED WITH 4 SKS OF CEMENT. NO CASING RECOVERY. PERFORATED CASING AT 503' AND 250'. RAN TUBING TO 500' AND SPOTTED 35 SKS OF CEMENT. PULLED TUBING FROM THE WELL, AND TIED ONTO CASING AND CIRCULATED CEMENT FROM 250'-0'.


Perfs:

Top	Bot	Thru	Comments
3669	3674	CSG	
3636	3640	CSG	

Remarks: CONSOLIDATED CEMENTING 60/40 4% GEL 3% CACL TA WELL

Plugged through: CSG

District: 02

Signed  (TECHNICIAN)
10/29/12

RECEIVED
OCT 05 2012
KCC WICHITA