

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20683
Spot: NESESE Sec/Twnshp/Rge: 12-33S-29W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: FELICE Well #: 1-12
County: MEADE Total Vertical Depth: 6183 feet

Operator License No.: 34322
Op Name: STRAT LAND EXPLORATION CO.
Address: 15 E. 5TH ST., STE 2020
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5390		WITH 2 SX CMT
PROD	5.5	6167	2600	WITH 300 SX CMT
SURF	8.625	1386		WITH 750 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2012 1:00 PM
Plug Co. License No.: 34572 Plug Co. Name: HOLMAN WELL SERVICE, LLC
Proposal Rcvd. from: BEN SMITH Company: HOLMAN WELL SERVICE, LLC Phone: (806) 665-2550

Proposed Plugging Method: SET CIBP @ 5390' WITH 2 SX CMT. PLUG AT 1420' WITH 15 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 09/28/2012 1:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 5390' WITH 2 SX CMT. 1ST PLUG AT 2596' WITH 50 SX CMT. 2ND PLUG AT 1445' WITH 100 SX CMT. TAG TOC @ 1393'. 3RD PLUG AT 1393' WITH 60 SX CMT. WOC 4 HOURS. TAG TOC @ 1305'. 4TH PLUG AT 738' WITH 100 SX CMT. 5TH PLUG AT 60' WITH 12 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5442	5450		

Remarks: USED COMMON CEMENT BY HOLMAN WELL SERVICE.

Plugged through: TBG

District: 01

Signed

(TECHNICIAN)

RECEIVED

OCT - 1 2012

KCC DODGE CITY

RECEIVED
OCT 09 2012
KCC WICHITA