

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21113-00-00  
Spot: S2NESWNW Sec/Twnshp/Rge: 8-10S-20W  
3580 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: WANKER B Well #: 1  
County: ROOKS Total Vertical Depth: 3960 feet

Operator License No.: 30553  
Op Name: UNREIN, GLENN DBA UNREIN OIL CO  
Address: 300 W 40TH ST  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3962		175 SX
SURF	8.625	158		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2012 1:30 PM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: AVEN WEAVERLING Company: AVEN'S CONSULTING Phone: (785) 623-3221

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/02/2012 5:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3698', pumped 170 sx cement w/300 # hulls.  
Pulled tubing to 2370', pumped 220 sx cement w/150 # hulls to circulate cement to surface.  
Pulled all tubing and topped off 5 1/2" casing w/35 sx cement.  
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 1/2 bbl water and pressured to 200 psi.  
GPS: 39.30266\*N, -099.10294\*

Perfs:

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 09 2012  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING TICKET # 6017

Plugged through: TBG

District: 04

Signed

Pat Bedore  
10/09/12 (TECHNICIAN)

CM

Form CP-2/3

OCT 09 2012