

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-01339-00-00
Spot: W2NWSWNW Sec/Twnshp/Rge: 21-12S-17W
3630 feet from S Section Line, 4980 feet from E Section Line
Lease Name: DREILING J P Well #: 3
County: ELLIS Total Vertical Depth: 3698 feet

Operator License No.: 33636
Op Name: TRIUNITED INVESTORS, LLC
Address: 18598 TWIN CREEKS RD
MONTE SERENO, CA 95030

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	2646		
PROD	5.5	3694		150 SX
SURF	8.625	221		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2012 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: JOHN FOSE Company: TRUUNITED INVESTORS Phone: (785) 623-0002

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Casing leaks @ 300' - 600'.
Perfs ARB: 3694' - 3697'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2012 1:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf tech shot 2 hole shoots at 1850', 1387', 848' and 210'.
Professional pulling services ran in hole with tubing to 1897', stacked out, pumped 6 bbl water to get through. Ran in hole to 3500'. Quality rigged to tubing and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 2507'. Quality rigged to tubing and pumped 150 sx cement w/200 # hulls to circulate cement up 4 1/2" liner.
Pulled tubing. Rigged to 4 1/2" casing and pumped 25 sx cement to pressure w/500 psi. Shut in pressure 400 psi.
Rigged to 8 5/8" casing, pumped 10 sx w/100 psi. Shut in pressure 100 psi.

Perfs:

Top	Bot	Thru	Comments
3694	3697		

Remarks: QUALITY WELL SERVICE KLV 31925

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

SEP 24 2012