

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-19257-00-00  
Spot: NWSWNENE Sec/Twnshp/Rge: 33-33S-11E  
4498 feet from S Section Line, 997 feet from E Section Line  
Lease Name: GRIFFITH Well #: 8  
County: CHAUTAUQUA Total Vertical Depth: 1150 feet

Operator License No.: 33157  
Op Name: R. D. ENERGY, INC.  
Address: 905 N MONTGOMERY  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1100		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/20/2012 8:00 AM

Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: ROD DICKENS Company: \_\_\_\_\_ Phone: (620) 725-3065

Proposed Plugging Method: PULL TBY & PKR. TIH W/ 1" TD, GELL HOLE, SPOT 100' PLUG ON BOTTOM. SET 50' MIDDLE PLUG @ 700'. PERFORATE CASING @ 350'. SET 350' CEMENT PLUG TO SURFACE INSIDE AND OUTSIDE OF CASING. CUT OFF AND CLEAN LOCATION.

Plugging Proposal Received By: DUANE SIMS

WitnessType: NONE

Date/Time Plugging Completed: 06/22/2012 10:00 AM

KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Ran 1" to 1150' gelled hole and spotted 15 sacks of cement. Pulled 1" and perforated casing at 700' and 350'. Ran 1" to 700' and spotted 15 sacks of cement. Pulled up to 350' and circulated cemen to surface inside and outside of casing. Pulled 1" and topped well off. A total of 170 sacks of cement were used to plug this well.

**Perfs:**

Top	Bot	Thru	Comments
1050	1100		PERU

RECEIVED  
OCT 09 2012  
KCC Chanute Dist #3  
DS  
RECEIVED  
OCT 11 2012

Remarks: WELL WAS PLUGGED DUE TO COMPLAINT FROM LANDOWNER

Plugged through: TBG

**KCC WICHITA**

District: 03

Signed Duane A Sims  
10/09/12 (TECHNICIAN)