

1 030576

15-165-20883-0000

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-NA

CNW, SEC. 13, T 16 S, R 18 W

3960 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6242

Lease Name Herman Well # 1

Operator: JULIUS LEGLEITER

County Rush 116.58

Name

Address 505 E 20th

Well Total Depth 3587 feet

Hays, Ks 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 1210

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Five Star Well Service License Number 7088

Address Box 953 Hays Ks. 67601

Company to plug at: Hour: 1:30 Day: 8 Month: 11 Year: 19 85

Plugging proposal received from J. LEGLEITER

(company name) J. LEGLEITER OIL CO. (phone) 913-625-0012

were: 4 1/2" set @ 3586 - Perfs from 3584 - 3046. Sand to 2950 + 45x cement on Perfs. Recover 1400' of 4 1/2" casing Top plug - Squeeze well through 8 7/8 plug return w/ 10 sx gel and 200 sx cement.

Plugging Proposal Received by Steve Dumont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 pm Day: 8 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT Sand Bottom perfs to 2950 + 45x cement through dump bailer.

Top plug - Squeeze 8 7/8" w/ 10 sx gel and 200 sx 6/40 Pozmix 67% gel. Shut in w/ 400 #.

Prod pressure 500 # Recovered 1400' of 4 1/2" casing.

Remarks: Cement by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED (if not) observe this plugging.

DATE DEC 11 1985

12-2-85
DEC 2 1985

Signed Steve Dumont
(TECHNICIAN)

INV. NO. 11438
71-8 DEC 16 1985

Petro-Log

Gamma Ray Neutron

COMPANY FOXFIRE EXPLORATION, INC.

WELL HERMANN #1

FIELD _____

COUNTY RUSH STATE KANSAS

Location C-NW/4

Other Services:

PERF.

Sec. 13 Twp. 16S Rge. 18W

Permanent Datum: GROUND LEVEL Elev. 2002
 Log Measured From K.B. 5 Ft. Above Perm. Datum
 Drilling Measured From KELLY RUSHING

Elev.: K.B. 2007
D.F.
G.L. 2002

Date	7/8/81				
Run No.	ONE				
Depth-Driller	3588				
Depth-Logger	3588				
Btm. Log Inter.	3587				
Top Log Inter.	3100				
Casing-Driller	8 5/8	@ 1135	4 1/2 @ 3548	100.4 @	
Casing-Logger	See Log				
Bit Size	7 7/8				
Type Fluid in Hole	WATER				
Dens.	Visc.				
pH	Fluid Loss	ml	ml	ml	ml
Source of Sample					
R ₁ @ Meas. Temp.	@	'F	@	'F	@
R ₂ @ Meas. Temp.	@	'F	@	'F	@
R ₃ @ Meas. Temp.	@	'F	@	'F	@
Source: R ₁ R ₂					
R ₄ @ BHT	@	'F	@	'F	@
Time Since Circ.					
Max. Rec. Temp.		'F		'F	
Equip.	Location	H-1	GB		
Recorded By	RAMEY				
Witnessed By	MD				

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 1 1981
 CONSERVATION DIVISION
 Wichita, Kansas