

AFFIDAVIT AND COMPLETION FORM


ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR CHIEF DRILLING CO., INC. API NO. 15-101-20,584-0000  
 ADDRESS 905 CENTURY PLAZA COUNTY Lane  
WICHITA, KANSAS FIELD DECATUR  
 \*\*CONTACT PERSON F.W. SHELTON, JR. LEASE ROEMER B  
 PHONE 316-262-3791

PURCHASER Clear Creek, Inc. WELL NO. #1  
 ADDRESS 818 Century Plaza Bldg. WELL LOCATION SE SW NW  
Wichita, Kansas 67202  
 DRILLING CONTRACTOR WARRIOR DRILLING, CO. 1,650 Ft. from the East Line and  
 ADDRESS 905 CENTURY PLAZA 330 Ft. from South Line of  
WICHITA, KANSAS 67202 the NW/4 SEC. 13 TWP. 16S RGE. 30W

PLUGGING CONTRACTOR \_\_\_\_\_  
 ADDRESS \_\_\_\_\_  
 TOTAL DEPTH 4401 PBTD 4399  
 SPUD DATE 11-30-81 DATE COMPLETED 1-4-82  
 ELEV: GR 2793 DF 2797 KB 2800



DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(AIR)~~ TOOLS (New) / ~~(used)~~ casing.  
 Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4	8 5/8	20#	326'	common	200	3% c.c. 2% gel
		4 1/2"	10.5#	4387'	AFC	200	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			None	None	None
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8"	4385'	None			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
treat w/250 gal. 15% reg. acid w/mud additives	4387 - 4399

TEST DATE: 1-12-82		PRODUCTION	
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity	
1-12-82	Pumping	34%	
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water
	35 bbls.	--	105 MCF
Disposition of gas (vented, used on lease or sold)		Producing interval (s)	
none		4387 - 4399	

\*\* The person who can be reached by phone regarding any questions concerning this information.  
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Unknown Depth \_\_\_\_\_  
 Estimated height of cement behind pipe 326'

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 Pawnee 4358 - 4401 30-30 30-30 strong blow diminishing to good. Rec. 360' GIP, 55' HOCM, 180' O - 10% M 270' O - 5% M, 85' O tr/W, 180' W - 10% O 400' W, IBHP: 1042, FBHP: 1042 FP: 102-577			Electric Log Tops	
			Anhydrite	2211
			Base Anhydrite	2231
			Heebner	3863
			Lansing	3898
			Muncie Creek SH.	4068
			BKC	4253
			Marmaton	4266
			Pawnee	4351
			Pawnee Pros.	4386
		T.D.	4399	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEDGWICK SS,


F.W. SHELTON OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS VICE PRESIDENT FOR CHIEF DRILLING CO., INC.  
 OPERATOR OF THE ROEMER B- LEASE, AND IS DULY AUTHORIZED TO MAKE THIS  
 AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS  
 BEEN COMPLETED AS OF THE 12th DAY OF January 19 82, AND THAT ALL  
 INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(s) F.W. Shelton, Jr.  
 F.W. SHELTON, JR., VICE PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 12th DAY OF January 19 82



Martha E. Gustin  
 NOTARY PUBLIC  
 Martha E. Gustin

MY COMMISSION EXPIRES: