

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-206360000

LEASE NAME HUBERT

WELL NUMBER #1-29

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

330 Ft. from S/N Line of Section (circle one)

660 Ft. from E/W Line of Section (circle one)

LEASE OPERATOR LANDMARK ENERGY EXPL., INC./Vess Oil Corp. SPOT LOCATION S/2 SW SW

ADDRESS 1861 N. Rock Rd. Suite 205 SEC. 29 TWP. 11 S. RGE 33 (X) or (W)

CITY, STATE, ZIP Wichita, Kansas 67206 COUNTY Logan

PHONE#(316) 683-8080 OPERATORS LICENSE NO. 06113 Date Well Completed 12-22-96

Character of Well D&A Date Plugging Commenced 12-22-96
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 12-22-96

The plugging proposal was approved on 12-22-96 (date)

by Ken Kuhn (KCC District Agent's Name)

Is ACO-1 filed? by oper. If not, is well log attached?

Producing Formation(s) Depth to Top Bottom T.D. 4641'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
surface		0	375'	8 5/8"	375'	none

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

25 sx. @ 2620', 100 sx. @ 1640', 40 sx. @ 430', 10 sx. @ 40', 15 sx. in rat-hole

Total: 190 sx. 60/40 Pozmix, 6% Gel, 1/4# floseal per sack Allied Cementing

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc.

License No. 6039

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Landmark Energy Exploration, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Bessie DeWerff (Employee of Operator or Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bessie DeWerff

(Address) R.R. 1 Box 183 B Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 26th day of December, 19 96

Rashell Patten
Notary Public

My Commission Expires: 2-2-99

Rashell Patten

NOTARY PUBLIC - State of Kansas
RASHELL PATTEN
My Appt. Exp. 2-2-99

RECEIVED
KANSAS CORP COMM
1996 DEC 31 12:11:48