

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-21,357-0000

LEASE NAME Keller

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 3

3020 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 6 TWP. 11 RGE. 19 (E or W)

COUNTY Ellis

LEASE OPERATOR Hellar Drilling Company, Inc.

711 Petroleum Bldg.

ADDRESS Wichita, KS 67202

PHONE (316) 267-2845 OPERATORS LICENSE NO. 5015

Date Well Completed 7/5/77

Character of Well oil

Plugging Commenced 12/9/87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/9/87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Lansing-KC Depth to Top 3380 Bottom 3604 T.D. 3705

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lans-KC	Oil & water	0	207	8 5/8	207	none
		0	3705	4 1/2	3705	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Down 4 1/2 @ 600# max pr mixed Flo seal w/25 sx cmt, then mixed 8 sx hulls w/225 sx cmt & SI @ 400#

Down annulus (8 5/8) @ 400# max pr mixed 2 sx hulls w/50 sx cmt & SI @ 150# 300 sx total

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co, Inc. License No. -

Address 24 S. Lincoln
Russell, KS 67665

STATE OF KANSAS COUNTY OF SWDGWICK, ss.

D. T. Heller - President - Hellar Drilling Company, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and that the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) D. T. Heller

(Address) 711 Petroleum Bldg.
Wichita, KS 67202


DEC 19 1987

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 87

Catherine Darcey
Notary Public - Catherine Darcey

My Commission Expires: March 25, 1988



HELLAR DRILLING COMPANY, INC.

711 PETROLEUM BUILDING
WICHITA, KANSAS 67202

D. L. HELLAR, PRESIDENT

December 17, 1987

TELEPHONE 267-2845

Re: Keller #3 Well
SW SW NW Sec. 6-11-19W
Ellis County, Kansas

State Corporation Commission
Oil & Gas Conservation Division
202 West 1st St. - Suite 200
Wichita, KS 67202


Gentlemen:

In connection with the captioned well we are enclosing
the following:

1. One (1) copy of Well Plugging Record (Form CP-4
Revised 08-84).
2. One (1) copy of Kansas Drillers Log.

Very truly yours,

HELLAR DRILLING COMPANY, INC.



D. L. Hellar

DLH:D
Encs.

RECEIVED
CORPORATION COMMISSION

DEC 18 1987
CONSERVATION DIVISION
Wichita, Kansas