

State of Kansas



15-05130317-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Miller of L.J. Dreiling & Sons Drlg. Inc. has this date requested permission to plug the following described well:

Mr. Niller guarantees payment of the plugging fee.

Operator's full Name: Zenith Drilling Corporation, Inc.

Complete Address: Suite 737-300 West Douglas, Wichita, Kansas

Lease Name: Keller Well No. 1

Location: SW SE NE Sec. 6 Twp. 11 Rge. 19 (E)(W) X

County Ellis Total Depth 3725 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

Gun pits, Circulate heavy mud, set cementing plug at 540'
and displace 25 sc cement thru drill pipe. Heavy mud to 100' set
cementing plug, 1/2 sc hulls and 20 sc cement thru drill pipe.
Heavy mud to 40' set cementing plug, 1/2 sc hulls and 18 sc
cement to base of celler. Plug rat hole with 2 sc cement.

Very truly yours,

L. W. Massey
Conservation Division Agent