



15-051-22710-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Tenny Building
WICHITA, KANSAS

RECEIVED
CORPORATION COMMISSION

MAR 15 1967

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Dave Hunt of Edsco Drlg. Corporation has this date requested permission to plug the following described well:

Operator's Full Name: Anatole Oil Corporation

Complete Address: 609 One Tandy Center, Fort Worth, Texas 76100

Lease Name: Joe Armbrister Well No. 1-5

Location: C of NW NW SW Sec. 5 Twp. 11 Rge. 19 (E) (W)

County: Ellis Total Depth: 3675'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Hunt was instructed to plug the well as follows:

8 5/8"-326' S.P. cuc. w/200 sacks 60/40 posmix-2% Gel.-3% CAL.CL.

Ordered 120 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @720' w/70 sacks cement

2nd plug @310' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @40' w/10 sacks cement.

Very truly yours,

Conservation Division Agent