



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 29 1968
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Cameran of H-30 Drlg. has this

date requested permission to plug the following described well:

Mr. Cameran guarantees payment of the plugging fee.

Operator's full Name: Hummom Oil, Inc.

Complete Address: 821 Union Nat'l Bldg. Wichita, Ks.

Lease Name: Vine "A" Well No. 2

Location: 100' W of NE SW NE Sec 35 Twp. 11 Rge. 19 (E)(W) X

County: Ellis Total Depth 3755 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameran was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 700' and displace
70 sc cement thru drill pipe. Heavy mud to 200' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug.
1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc
cement.

Very truly yours,

 Conservation Division Agent