

AFFIDAVIT AND COMPLETION FORM

ACO-1


This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Wamego Oil, Inc. API NO. 15-051-22, 424-000
 ADDRESS 270 Research Drive, Suite "G" COUNTY Ellis
Manhattan, Kansas 66502 FIELD Perfas
 **CONTACT PERSON Harold Sadownik LEASE Latilda Albert

PHONE (913) 537-4100
 PURCHASER Koch Oil Company WELL NO. One
 ADDRESS P. O. Box 2256 WELL LOCATION N.E. Quarter
Wichita, Kansas 67201 450 Ft. from South Line and
 300 Ft. from East Line of

DRILLING CONTRACTOR Kanor Drilling Company the N&E SEC. 30 TWP. 11s RGE. 19E.
 ADDRESS P. O. Box 85

May, Kansas 67511
 PLUGGING CONTRACTOR None
 ADDRESS N/A
 TOTAL DEPTH 300' PBTD _____
 SPUD DATE 1-1-81 DATE COMPLETED 10-23-81
 ELEV: GR21.0 DF21.2 KB21.5'



WELL PLAT
 (Quarter) or (Full) Section -
 Please indicate.

KCC
 KGS
 MISC.

DRILLED WITH (CABLE (ROTARY) (AIR) TOOLS
 Report of all strings set - surface, intermediate, production, etc. (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8-5/8"	24#	247'	Common	100	GEL 3 SKS Chloride 5 SKS
Production	7-7/8"	5 1/2"	14#	3058'	Common	130	Cal 21 367 lbs GEL 245 lbs

LINER RECORD			PERFORATION RECORD		
Top ft.	Bottom ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None	N/A	N/A	None	N/A	N/A
TUBING RECORD					
Size	Setting depth	Packer set at			
2 1/2" O.U.L.	3555	None			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
NONE	N/A

TEST DATE: 10-17-81 PRODUCTION STAB 84 BO in 4 hrs; no water
 Date of first production 10-23-81 Producing method (flowing, pumping, gas lift, etc.) Pumping A.P.I. Gravity 26
 RATE OF PRODUCTION PER 24 HOURS Oil 135 bbls. Gas None MCF 1.2 % Water bbls. Gas-oil ratio N/A CFPB
 Disposition of gas (vented, used on lease or sold) Used on lease. Producing interval(s) Arbuckle - Open Hole

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Buried river bed Depth 100'
 Estimated height of cement behind pipe 600'

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
Anhydrite	1454'	+551	+607	R.A. Guard Electric Log	3654'
Heebner	3314'	-1209			
Toronto	3332'	-1227			
Lansing, NO	3354'	-1249	-1468		
Marmaton	3602'	-1503			
Conglomerate	3622'	-1517			
Arbuckle	3657'	-1552			
<p>Drill Stem Test Report enclosed</p>					
<p>USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.</p>					

A F F I D A V I T

STATE OF Kansas, COUNTY OF Geary SS,

Harold G. Sadowski OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS


OATH, DEPOSES AND SAYS:

THAT HE IS Vice-President FOR Wamego Oil, Inc.
 OPERATOR OF THE Matilda Albert LEASE, AND IS DULY AUTHORIZED TO MAKE THIS
 AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. One ON SAID LEASE HAS
 BEEN COMPLETED AS OF THE 23rd DAY OF October 19 81, AND THAT ALL
 INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Harold G. Sadowski

SUBSCRIBED AND SWORN TO BEFORE ME THIS 5 DAY OF Nov 19 81



Jewell K. Warner
NOTARY PUBLIC

MY COMMISSION EXPIRES: