

15-051-22710-0000

RECEIVED  
STATE CORPORATION COMMISSION  
FORM CP-4  
Rev. 12-15-80  
APR 14 1982  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ellis SEC. 5 TWP. 11S RGE. 19W E/W  
Location as in quarters or footage from lines:  
NWNWSW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Anatole Oil Corporation  
Lease Name Joe Armbrister Well No. 1-5  
Office Address 609 One Tandy Center, Ft. Worth, Texas 76102  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 3-12-82  
Application for plugging filed 3-12-82  
Plugging commenced 3-12-82  
Plugging completed 3-12-82  
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scheck

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Formation	Content	From	To	Size	Casing Record	
					Put in	Pulled Out
Surface	.328' of 8-5/8"	200sks.	3%CC	2%Gel		

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

70sks. @720'  
40sks. @310'  
10sks. @40'  
50/50 pos mix, 4%Gel 3%CC

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EDSCO Drilling  
Hayes, Kansas

STATE OF Texas COUNTY OF Tarrant, ss.

Robert D. Baker (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Robert D. Baker  
609 One Tandy Center, Ft. Worth, Texas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of March, 19 82

My Commission expires: MY COMMISSION EXPIRES 12-29-84  
Chris Paender Notary Public.

EDSCO DRILLING CORP  
DRILLER'S WELL LOG

RECEIVED  
STATE CORPORATION COMMISSION  
APR 14 1982  
CONSERVATION DIVISION  
Wichita, Kansas

Armbrister # 1-5  
NWMWSW-5-11S-19W  
Ellis County, Kansas


Commenced: 3-5-82  
Completed: 3-12-82

OPERATOR: ANATOLE OIL CORPORATION

Depth		Formation	Remarks
From	To		
0	328	Sand-Shale	Ran 328' of 8-5/8" casing cemented w/200 sks common 2% Gel 3%CC
328	1185	Sand-Shale	
1185	1943	Sand-Shale	
1943	2556	Shale-Lime	
2556	3149	Lime-Shale	
3149	3583	Shale-Lime	
3583	3715TD	Lime-Shale	

STATE OF TEXAS )  
                          )SS  
COUNTY OF TARRANT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

EDSCO DRILLING CORP  


Subscribed and sworn to me this 25 day of March, 1982

My Commission Expires MY COMMISSION EXPIRES 12-29-85

