


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Logan County, Sec. 22 Twp. 11S Rge. 32W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C NE NW

Lease Owner DNB Drilling, Inc., Reed, Aladdin Pet. Cor.
Lease Name Cooper Well No. 1
Office Address 515 R. H. Garvey Bldg., Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Date Well completed 3-11 1977
Application for plugging filed 3-11 1977
Application for plugging approved 3-11 1977
Plugging commenced 3-11 1977
Plugging completed 3-11 1977
Reason for abandonment of well or producing formation
No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4690
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS						CASING RECORD	
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT	
Surface Hole	Shale	Surf	328	8-5/8"	320	None	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3-30-77

Fluid to 1550', plug, 60 sx cement;
Fluid to 300', plug, 20 sx cement;
Fluid to 40', plug, 1/2 sx hulls, 10 sx cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor DNB DRILLING, INC. DNB DRILLING, INC.
701 First National Building 515 R. H. Garvey Building
Wichita, Kansas 67202 Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF ss.
JAMES L. DONELSON (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
515 R. H. Garvey Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of March, 1977

Ella Priess
Notary Public.

My commission expires Aug. 25, 1980

Ella Priess



DRILLERS' LOG

D N B DRILLING, INC., REED and
ALADDIN PETROLEUM CORPORATION

No. 1 Cooper
C NE NW, Sec. 22-11E-22W
Logan County, Kansas

Elev: 3031 K.B.

Commenced: 3-3-77
Completed: 3-11-77

Surface Casing: 320' of
8-5/8" cemented w/225 sg
cement, 28 Gal, 38 cc.
3-3-77

FORMATIONDEPTH

Surface Hole	0 - 320
Sand & Shale	328 - 1450
Shale & Sand streaks	1450 - 2045
Red Bed	2045 - 2096
Anhydrite	2096 - 2127
Shale	2127 - 2885
Shale & Red Bed	2885 - 3045
Lime & Shale	3045 - 4125
Lime	4125 - 4235
Lime & Shale	4235 - 4300
Lime	4300 - 4475
Lime & Shale	4475 - 4540
Lime	4540 - 4690 RTD

I do hereby certify that the foregoing statements are true and correct
to the best of my knowledge and belief.

D. N. B. DRILLING, INC.

James L. Dowelson
JAMES L. DOWELSON

STATE OF KANSAS; ss:

Subscribed and sworn to before me this 28th day of March 1977.

Ella Priess
Ella Priess, Notary Public

