


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Logan County, Sec. 22 Twp. 11 Rge. 32 E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
C SE NE

Lease Owner Aladdin Petroleum Corporation  
Lease Name Cooper Well No. 1  
Office Address 809 Petroleum Bldg., Wichita, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202  
oil



Locate well correctly on above  
Section Plat

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced August 27 1979  
Plugging completed August 29 1979  
Reason for abandonment of well or producing formation  
depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor  
Producing formation Depth to top Bottom Total Depth of Well 4675'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			314'	8 5/8"	314'	none
			4674'	4 1/2"	4674'	1527.26

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Pushed plug to 4050'. Sanded back to 4025' and dumped 5 sacks of cement.

Halliburton Services plugged well pumping in 3 sacks of hulls, 21 sacks  
of gel and 130 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 5 1979


(If additional description is necessary, use BACK of this form)  
Name of Plugging Contractor GLENNS CASING PULLING INC.  
Box 413, Ellinwood, Kansas 67526  
Wichita, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.  
Evelyn Roth (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 1979



My commission expires

Jenny Kasselmann  
Notary Public.

## DRILLERS LOG

COMPANY: Aladdin Petroleum Corporation  
809 Petroleum Building  
Wichita, Kansas 67202

LEASE: Cooper No.1  
C SE NE Section 22-11S-32W  
Logan County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
408 One Twenty Building  
Wichita, Kansas 67202

TOTAL DEPTH: 4675'

COMMENCED: January 21, 1975

COMPLETED: January 29, 1975

CASING: 307' of 8-5/8" set with 250 sacks Cement  
Ran 148 Jts. of 4½" casing set with 250 sacks. (4,692.11')  
plug down 2:45 a.m. January 29, 1975.

0' to 60'	Sand and Shale
60' to 314'	Surface hole
314' to 2541'	Shale & Shells
2541 to 2577'	Anhydrite
2577' to 3030'	Shale & Shells
3030' to 4013'	Shale & Lime
4013' to 4675'	Lime
4675'	RTD

RECORDED  
AUG 14 1979  
WICHITA, KANSAS

STATE OF KANSAS  
COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.  
upon oath state that the above and foregoing is a true and correct copy of  
the log of the Cooper No.1.



*James C. Remsberg*

Subscribed and sworn to me on February 6, 1975.

*Mary Lou Taylor*  
Mary Lou Taylor, Notary

My commission expires January 17, 1977