


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Logan County. Sec. 13 Twp. 11 Rge. 33W (XXXXXXX)
Location as "NE/CNW/SE" or footage from lines NE SW SE
Lease Owner DONALD C. SLAWSON
Lease Name Kruse 'C' Well No. 2
Office Address 200 Douglas Building Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 5, 19 79
Application for plugging filed January 5, 19 79
Application for plugging approved January 5, 19 79
Plugging commenced January 5, 19 79
Plugging completed January 5, 19 79
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4750 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	292.42	surface	300'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug @ 1600' w/70 sx
2nd plug @ 280' w/20 sx
Solid Bridge @ 40' w/10 sx
2 sx in Rat Hole

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Slawson Drilling Co., Inc.
Address 200 Douglas Building Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. J. THATCHER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. THATCHER 200 Douglas Bldg. Wichita, KS
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of March, 19 79

My commission expires 6/12/82

SHERRY L. MILFORD
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appl. Exp. 6/12/82

Sherry L. Milford
Notary Public.

WELL LOG

OPERATOR: DONALD C. SLAWSON
 200 Douglas Building
 Wichita, Kansas. 67202

LEASE: #2 Kruse 'C'
 NE SW SE Sec. 13-11-33W
 Logan County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: December 28, 1978

COMPLETED: January 5, 1979

CASING: Surface - 8 5/8" @ 300' w/225 sx 60/40 poz

0 - 305 Shale and sand
 305 - 1027 Shale
 1027 - 1993 Shale and sand
 1993 - 2337 Shale and Shells
 2337 - 2594 Shale
 2594 - 2621 Anhydrite
 2621 - 3050 Shale and Lime
 3050 - 4031 Lime and Shale
 4031 - 4397 Lime
 4397 - 4632 Lime and Shale
 4632 - 4715 Lime
 4715 - 4750 Lime and Shale
 4750 RTD

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

SS.

RECEIVED
 STATE COMMISSION
 MAR 21 1979
 CONSERVATION DIVISION
 Wichita, Kansas

I, R.J. Thatcher, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the #2 Kruse 'C' test.

R.J. Thatcher
 R. J. Thatcher, Engineer

Subscribed and sworn to before me this 9th day of March, 1979.

Sherry L. Milford
 Sherry L. Milford, Notary Public

My Commission Expires: 6/12/82

