

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 6 Twp. 11 Rge. 19 (XXXXXX)(W)

Location as "NE/CNW/SW" or footage from lines NE NW SW

Lease Owner M. P. Gilbert

Lease Name Armbrister Well No. 1

Office Address c/o M. J. Lebsack #9 Lee Bldg. 2133 S. Bellaire, Denver, Colo. 22

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 14 19 65

Application for plugging filed May 14 19 65

Application for plugging approved May 14 19 65

Plugging commenced May 14 19 65

Plugging completed May 14 19 65

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3750 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Clay - Shale	0	225	8 5/8"	140'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug set at 540' with 20 sacks cement.

Plug set at 180' with 20 sacks cement.

Plug set at 35' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company

Address 650 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS

COUNTY OF SEDGWICK

ss.

contractor

Dan J. Kornfeld

(Signature) \_\_\_\_\_ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Dan J. Kornfeld  
650 Fourth Natl. Bank Bldg., Wichita, Ks. 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of May 19 65

My commission expires September 14, 1968.

Sandra Kay Peer  
Sandra Kay Peer

Notary Public.

L O G

COMPANY: M. P. Gilbert  
 CONTRACTOR: Empire Drilling Company  
 FARM: Armbrister #1  
 LOCATION: NE NW SW Section 6-11-19W, Ellis County, Kansas  
 COMMENCED: May 7, 1965 ELEVATION: 2113 KB  
 COMPLETED: May 14, 1965 POTENTIAL: D & A

\*\*\*\*\*

0	to	225	Surface - Clay - Shale
225	to	1285	Shale & Sand
1285	to	1491	Redbed - Shale
1491	to	1531	Anhydrite
1531	to	1566	Shale & Shells
1566	to	1820	Shale
1820	to	2105	Shale & Shells
2105	to	2440	Shale - Lime
2440	to	2605	Lime
2605	to	3305	Lime & Shale
3305	to	3375	Lime
3375	to	3420	Lime & Chert
3420	to	3495	Lime
3495	to	3550	Lime & Shale
3550	to	3570	Lime
3570	to	3645	Lime-Shale
3645	to	3710	Lime & Shale Chert
3710	to	3750	Shale & Arbuckle
3750			Rotary Total Depth

SET: 140' of 8 5/8" with 75 sacks cement.

WELEX ELECTRIC LOG TOPS:

Topeka	3127	-1014
Heebner	3348	-1235
Toronto	3369	-1256
Lansing	3387	-1274
Base Kansas City	3604	-1491
Basal Pennsylvanian Conglomerate	3650	-1537
Simpson	3703	-1590
Arbuckle	3717	-1604
Welex Total Depth	3748	


RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1965


CONSERVATION DIVISION  
Wichita, Kansas

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Armbrister #1, NE NW SW Section 6-11-19W, Ellis County, Kansas, as reflected by the files of Empire Drilling Company.

  
 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 18th day of May, 1965.

  
 Sandra Kay Peer, Notary Public

My commission expires September 14, 1968.