

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Logan SEC. 13 TWP. 11S RGE. 32W E/W
Location as in quarters or footage from lines:
NW NW

Locate Well
correctly on above
Section Platt.

Lease Owner George R. Jones
 Lease Name PIONEER Well No. 4
 Office Address 125 N. Market, Suite #1210, Wichita, KS 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed May 9, 1982
 Application for plugging filed May 9, 1982
 Plugging commenced May 9, 1982
 Plugging completed May 9, 1982
 Reason for abandonment of well or producing formation No commercial quantity of oil or gas encountered.
 Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
 Producing formation _____ Depth to top _____ bottom T.D. 4535'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Formation	Content	From	To	Size	Put In	Casing Record
						Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 1600' with 80 sx.
Set 2nd plug @ 300' with 40 sx.
Set 3rd plug @ 40' Sol. Bridge with 10 sx.
10 sx. in Rahole. 50-50 posmix. 4% gel. 1% c.c.
Plug was down @ 8:00 a.m., 5/09/82.

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1982
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
 801 Union Center, Wichita, KS 67202
 (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 19 82

My Commission expires: 7-13-85

Elizabeth G. Terry
 Elizabeth G. Terry Notary Public
 NOTARY PUBLIC
 STATE OF KANSAS

MAY 14 1982

CONTRACTORS WELL LOG

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

George R. Jones
Abercrombie Drilling, Inc.
PIONEER #4
NW NW, Sec. 13-11S-32W
Logan County, Kansas
5/01/82
5/09/82

0	150	Clay & Sand
150	290	Shale
290	2500	Shale & Sand
2500	2548	Anhydrite
2548	3875	Shale
3875	4065	Shale & Lime
4065	4200	Lime & Shale
4200	4535	Lime
	4535	Rotary Total Depth

Spud @ 2:00 p.m., 5/01/82. Drilled 290' of a 12 1/2" hole. Ran 7 jts. of 8 5/8" 20# casing (tally 279.28') set @ 286' and cemented with 200 sx. 60-40 posmix, 2% gel, 3% c.c. Cement did circulate. Plug was down @ 6:15 p.m., 5/01/82.

4535' TD. Set 1st plug @ 1600' with 80 sx. Set 2nd plug @ 300' with 40 sx. Set 3rd plug @ 40' Sol. Bridge with 10 sx. 10 sx. in Rathole. 50-50 posmix, 4% gel, 1% c.c. State plugger Carl Goodrow. Plug was down @ 8:00 a.m., 5/09/82.

RECEIVED
STATE CORPORATION COMMISSION

SAMPLE TOPS:

Anhydrite 2500'
B/Anhydrite 2548'

MAY 17 1982

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack K. Wharton, Asst. Secy./Treas. for Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the PIONEER #4, NW NW, Sec. 13-11S-32W, Logan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack K. Wharton
Jack K. Wharton, Asst.
Secy./Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 12th day of May, 1982.

Elizabeth G. Terry
Elizabeth G. Terry
NOTARY PUBLIC

my commission expires 7-13-85

