

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission,
800 Bitting Building,
Wichita, Kansas

No

ELLIS

County. Sec. 6 Twp. 11 Rge. 19 (E) (W)

Location as "NE¼NW¼SW¼" or footage from lines SE-SW¼

Lease Owner. J.E. TRIGG ET AL

Lease Name. ARMMASTER Well No. 1

Office Address. 1109-1st Natl Bldg Okla City Okla

Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date, well completed July 7th 36 1936

Application for plugging filed 1936

Application for plugging approved 1936

Plugging Commenced July 7th 1936

Plugging Completed July 8th 1936

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 1936

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes Mr Alexander

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3770 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	125	12 1/4	125 ft	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy rotary mud was pumped in hole and a plug set at 125 ft (bottom of surface casing) and cement placed on it. Another plug set just below bottom of cellar and cemented. Surface casing was cut off in bottom of cellar and a piece of boiler plate welded over it.

jd 7/16/36

6 11 1936
53 24

(If additional description is necessary use BACK of this sheet)

Correspondence regarding this well should be addressed to
Address 1109-1st Natl Bldg J.E. Trigg

Okla City Okla

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

J.E. Trigg (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.E. Trigg

Okla City Okla (Address)

SUBSCRIBED AND SWORN to before me this 10th day of July 1936

My commission expires May 10, 1939
Garry Sewell Notary Public

LOG OF WELL #1

ARMBRISTER LEASE,

SE SW $\frac{1}{4}$ Sec 6 - 11S - 19W,
Ellis County, Kansas.

Surface	0 - 125	
Red Beds	125 - 890	
Sandy Shale	890 - 950	
Lime	950 - 980	
Sand & Shale	980 - 1250	
Red Beds	1250 - 1500	
Lime	1500 - 1560	Anhydrite.
Red Rock	1560 - 1580	
Shale & Shells	1580 - 2040	
Red Rock	2040 - 2055	
Shale	2055 - 2077	
Lime	2077 - 2164	
Shale	2164 - 2170	
Shale & Shells	2170 - 2488	
Lime	2488 - 2550	
Shale	2550 - 2580	
Lime	2580 - 2680	
Shale	2680 - 2710	
Lime	2710 - 2785	
Shale & Shells	2785 - 2970	
Lime	2970 - 2990	
Shale	2990 - 3000	
Lime	3000 - 3110	
Shale	3110 - 3120	
Lime	3120 - 3280	
Shale	3280 - 3285	
Lime	3285 - 3314	
Shale	3314 - 3320	
Lime	3320 - 3337	
Shale & Shells	3337 - 3420	
Lime	3420 - 3660	Kansas City.
Shale	3660 - 3710	
Lime	3710 - 3763	Simpson.
Lime	3763 - 3770	Siliceous.

6 11 19W
53 24