

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

Ellis County, Sec. 6 Twp. 11 Rge. (E) 19 (W)

Location as "NE/CNWxSWx" or footage from lines W/2W/2SE

Lease Owner Three G Oil, Inc.

Lease Name Armbrister Well No. 1

Office Address 700 Brown Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed August 25, 19 67

Application for plugging filed 19

Application for plugging approved May 6, 19 70


Plugging commenced May 7, 19 70

Plugging completed May 8, 19 70

Reason for abandonment of well or producing formation Not economical to produce

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation Lansing-Kansas City Depth to top 3415 Bottom 3633 Total Depth of Well 3740 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1970
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

RTD 3740' 8 5/8 csg. set at 206' cwc 150 sk.
5 1/2 csg. set at 3570' cw 100 sk. cement
5 1/2 csg. perf. (3450-3452) and (3495-3497)
5 1/2 csg. DV tool set at 1524 and cemented with 500 sk. cement
No pipe recovered
Pumped thru 5 1/2 plug container with 30 sk. poz 6% gel, 30 sk. gel with 5 sk. hulls, plug and 60 sk. poz 6% gel. Maximum pressure 2500 lbs.
Checked Anulus (8 5/8 - 5 1/2)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing

Address Hays, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
A. J. Gebert (employee of owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. J. Gebert President

700 Brown Building, Wichita, Kansas 67202 (Address)

Subscribed to before me this 26th day of May 19 70

April 22, 1974



Glenna M. Clements Notary Public.

15-051-20086-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **Three G Oil, Inc.**
FARM **Ambrister** NO. **1**

SEC. **6** T. **11S.** R. **19W**
LOC. **W/2 W/2 SE**

TOTAL DEPTH **3,740'**
COMM. **July 8, 1967**
SHOT OR TREATED
CONTRACTOR **H-30, Inc.**
ISSUED

COMP. **July 19, 1967**

COUNTY **Ellis**



CASING

20 15 12 13	10 8-5/8" 190' cemented w/125 sacks cement 6 5-1/2" 3,570' cemented w/100 sk cement; D.V. Tool @ 1940' w/500 sk cement	ELEVATION 2153 KB PRODUCTION
----------------------	--	------------------------------------

FIGURES INDICATE BOTTOM OF FORMATIONS

		<u>SAMPLE TOPS</u>	
Surface Clay & Post Rock	40		
Shale	990	Anhydrite	1526 * 627
Sand	1240	Anhydrite Case	1575 * 573
Red Bed	1526	Topoka	3153 - 1005
Anhydrite	1575	Queen Hill	3303 - 1155
Shale	2030	Heebner	3375 - 1223
Lime & Shale	2620	Toronto	3397 - 1244
Shale w/Lime Streaks	2775	Lansing	3416 - 1263
Lime & Shale	3270	Base K. C.	3633 - 1400
Lime	3636	Conglomerate	3636 - 1533
Chert	3700	Simpson	3695 - 1542
Sand	3730	Simpson Sand	3700 - 1547
Lime	3740	Arbuckle	3730 - 1577
Rotary Total Depth	3740	Rotary T D	3740 - 1587

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
Arlo B. Romer

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1970
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS }
COUNTY OF SEDGWICK } 99

Subscribed and Sworn to before me a Notary Public in and for said county and state this 20th day of July, 1967.

Martha Hartpence
Martha Hartpence - Notary Public

My Commission Expires: April 21, 1971