

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 6 Twp. 11S Rge. (E) 19 (W)  
Location as "NE/CNW/SW" or footage from lines NW/4 SW/4 NE/4  
Lease Owner K. S. Martin, et al  
Lease Name Keller Well No. 1  
Office Address 527 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 11, 19 56  
Application for plugging filed (verbal) September 11, 19 56  
Application for plugging approved (verbal) September 11, 19 56  
Plugging commenced September 11, 19 56  
Plugging completed September 11, 19 56  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3750 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None	None	0	195'	8 5/8"	192'	None
No oil string -	D & A					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 190', set bottom plug at 190' with 15 sacks cement and 1/2 sack Hulls.

Filled hole with heavy mud to 40', set top plug at 40' with 10 sacks cement and 1/2 sack Hulls

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.  
Address 510 Orpheum Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Robert F. Walters (employee of owner) or ~~(owner)~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters

510 Orpheum Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 56

My commission expires March 10, 1960

Pauline Hadueken  
Notary Public.

9-20-56

PLUGGING  
FILE SEC 6 T 11 R 19W  
BOOK PAGE 98 LINE 35

KELLER NO. 1

LOCATION: NW/4 SW/4 NE/4 Sec. 6-11S-19W, Date Spudded: 8-31-56  
 Ellis County, Kansas  
 Completion: 9-11-56

OPERATOR: K. S. Martin  
 Elevation: 2109 Gr

CONTRACTOR: Walters Drilling Co. 2111 DF  
 2114 KB

SURFACE CASING: 8 5/8" set at 195' with  
 150 sacks cement and  
 2 Cal. Chloride

OIL STRING: None. D & A

L O G

(Figures indicate bottom of formation)

Surface	0 to 195
Shale	215
Shale and Shells	955
Sand	1202
Shale and Shells	1490
Anhydrite	1528
Shale and Shells	1562
Shale and Red Bed	1900
Shale and Shells	2050
Shale and Lime	3478
Lime	3527
Lime and Shale	3750
Total Depth	3750

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

By Robert F. Walters

Subscribed and sworn to before me  
 this 12th day of September, 1956

Pauline Rudickson  
 Notary Public

My commission expires:  
 March 10, 1960

RECEIVED  
 SEP 10 1956  
 WALTERS DRILLING CO.

PLUGGING			
FILE	SEC	6 T. 11 R. 19W	
BOOK	PAGE	98	LINE 35