

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County, Sec. 6 Twp. 11 Rge. 19W (W)

Location as "NE/CNW&SW" or footage from lines SW SW NW

Lease Owner Ross Welch

Lease Name Keller Well No. 1

Office Address 1509 Briggs Ave. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed November 19 53

Application for plugging filed March 2, 19 59

Application for plugging approved March 3, 19 59

Plugging commenced April 10, 19 59

Plugging completed April 10, 19 59

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3718' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8 5/8" at 137' circulated with cement - 5 1/2" 3697' with 125 sacks cement behind. Lane wells plugs to 3504', perforated 3425'. Filled with sand to 3410', set 4 sacks cement with dump bailer, pulled 800' 5 1/2" to 600', circulated hole with heavy mud, displaced 20 sacks cement through 5 1/2" at 600', heavy mud to 180', displaced 20 sacks cement through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sacks cement to bottom cellar. Mudding and cementing by Globe Cementing Co.

RECEIVED  
STATE CORPORATION COMMISSION

APR 1 1965  
OK OI

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wiggins & Lamb

Address McPherson, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.  
Ross Welch (employee of owner) or (operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Signature]

Box 295 Independence, Kas (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of March 19 65

Margaret M. Kaufman Notary Public.

My commission expires 4/18/67



Locate well correctly on above Section Plat

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company- HEATHMAN & CO.  
Farm- Kellor No. 1

SEC. 6 T. 11 R. 19W  
SW SW NW

Total Depth. 3718  
Comm. 11-4-51 Comp. 11-15-51  
Shot or Treated.  
Contractor. Heathman & Co.  
Issued. 1-26-52

County Ellis KANSAS



Elevation. 2131 DE

Production. Pot. 178 BO & 10% W.

Figures Indicate Bottom of Formations.

shale	136	
sand & shale	980	
sand	1232	
shale	1510	
anhydrite	1553	
shale & shells	2131	
lime & shale	2554	
lime	2660	
shale & lime	2886	
shale	3000	
shale & lime	3240	
lime	3300	
lime & shale	3471	
lime	3480	
lime & shale	3700	RTD
lime	3718	
Total Depth		

Tops: KB	
Anhydrite Corr.	1510
Topeka	3132
Hebner	3346
Lansing-Kansas City	3385
Arbuckle	3696

RECEIVED  
STATE CORPORATION COMMISSION

MAR 29 1953

CONSERVATION DIVISION  
Wichita, Kansas

## W E L L L O G

COMPANY: Heathman Oil (Ross Welch)  
 LEASE: Keller Well No. 1  
 LOCATION: SW SW NW Sec. 6 - 11 - 19 W , Ellis County  
 COMPLETED: Nov. , 1953 ELEV.:

---

8 5/8" Sur. Casing Cem. w/ 120 sacks @ 137'

6 1/2" 14# Smls. casing Cem. w/ 125 sacks @ 3697'

Total Depth 5718'

Plugged back to 3504'

Perforating record:

3425' to 3429'  
 3438' to 3443'  
 3461' to 3464'  
 3469' to 3472'

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 5 1959

CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING

FILE SEC 6 T 11 R 19W  
 BOOK PAGE 16 LINE 39