

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 35 Twp. 11 Rge. 19W (E) (W)

Location as "NE/CNWxSWx" or footage from lines NE SW SE

Lease Owner J. F. Darby Oil Co., Oil Trading Assoc. Inc. & C-G Drilling Co. #1
Lease Name Steckline "B" Well No.

Office Address 1807 Philtower Building, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 21 1958

Application for plugging filed July 21 1958

Application for plugging approved July 21 1958

Plugging commenced July 21 1958

Plugging completed July 21 1958

Reason for abandonment of well or producing formation Too low structurally.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3710' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	204.73'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 500'. Set plug. Put in 20 sacks cement. Filled to 195'. Set plug. Put in 1/2 sack hulls and 15 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G DRILLING CO.
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1958

My commission expires March 22, 1960
Celeste B. Romine Notary Public.

8-7-58 AUG 7 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 35 T. 11 R. 19W
BOOK PAGE 118 LINE 41

CONTRACTOR'S WELL LOG

OPERATOR J. F. Darby Oil Co., Oil Trading Assoc., Inc., & C-G Drilling Co. WELL NAME Steckline "B" #1
 LOCATION NE SW SE SEC. 35-11-19W RIG NO. 2
 COUNTY Ellis STATE Kansas
 COMMENCEMENT DATE July 10, 1958 COMPLETION DATE July 21, 1958

LOG OF WELL

Elevation 2110' rotary bushing.
 All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	204	Shale-Sand		
204	805	Shale-Sand		
805	925	Shale-Sand		
925	1125	Sand		
1125	1443	Red Bed		
1443	1478	Anhydrite		
1478	1755	Shale-Shell		
1755	2000	Shale-Shell		
2000	2190	Shale-Lime		
2190	2375	Shale-Lime		
2375	2460	Shale-Lime		
2460	2595	Shale-Lime	0° - 2500	
2595	2762	Shale-Lime	0° - 2750	
2762	2920	Shale-Lime		
2920	3050	Shale-Lime	0° - 3000	
3050	3136	Shale-Lime		
3136	3218	Lime		
3218	3291	Lime	0° - 3250	
3291	3332	Lime		
3332	3394	Lime		
3394	3458	Lime		DST 3424-3465'
3458	3465	Lime		
3465	3489	Lime		
3489	3535	Lime		
3535	3595	Lime		
3595	3655	Lime		
3655	3666	Lime		
3666	3670	Arbuckle		DST 3666-3670'
3670	3673	Arbuckle		DST 3668-3673'
3673	3676	Arbuckle		DST 3672-3678'
3676	3678	Arbuckle		
3678	3702	Arbuckle		
3702	3710	Arbuckle		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 204.73' (10 jts.) 8-5/8" OD Surface Casing.

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

PLUGGING			
FILE SEC.	35	T. 11	19W
BOOK	PAGE 18	LINE	41

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
 G. F. Galloway

SUBSCRIBED AND SWORN TO BEFORE ME THIS 24th day of July, 1958.

My commission expires: March 22, 1960

Celeste B. Romine
 Celeste B. Romine, Notary Public