

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, GWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.


OPERATOR Abercrombie Drilling, Inc. API NO. 15-109-20,199-0000
 ADDRESS 801 Union Center COUNTY Logan
Wichita, KS 67303 FIELD _____
 **CONTACT PERSON _____ LEASE MOORE 'C'
 PHONE _____

PURCHASER _____ WELL NO. 1
 ADDRESS _____ WELL LOCATION C NE SE
 _____ 660 Ft. from North Line and
 _____ 660 Ft. from East Line of
 the 33 SEC. 11S TWP. 33W RGE.

DRILLING CONTRACTOR Abercrombie Drilling, Inc.
 ADDRESS 801 Union Center
Wichita, KS 67202

PLUGGING CONTRACTOR Abercrombie Drilling, Inc.
 ADDRESS 801 Union Center, Wichita, KS 67202

TOTAL DEPTH 4650' PBTD _____
 SPUD DATE 11/09/81 DATE COMPLETED 11/21/81
 ELEV: GR 3065 DF 3068 KB 3070'



DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS
 Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing.


Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Types and percent additives
Surface	12 1/2"	8 5/8"	20#	327'	Common	240	2% gel, 3% c.c

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Size	Setting depth	Fracker set at	Depth interval treated

TEST DATE:				PRODUCTION			
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity		Rate of production per 24 hours		Gas-oil ratio	
Disposition of gas (vented, used on lease or sold)		Producing interval (s)					

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 20 BOPD or is located in a Basic Order Pool.



Name of lowest fresh water producing stratum UNKNOWN Depth _____
 Estimated height of cement behind pipe Cement did circulate to surface.

WELL LOG

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
			NAME	DEPTH
Surface Clay & Sand	0	331	<u>SAMPLE TOPS:</u>	
Sand & Shale	331	1856	Anhydrite	2559' (+ 511)
Shale & Sand	1856	2056	B/Anhyd.	2588' (+ 482)
Sand	2050	2095	Heebner	3969' (- 899)
Shale	2095	2559	Toronto	3996' (- 926)
Anhydrite	2559	2588	Lansing	4014' (- 944)
Shale	2588	3883	Stark	4232' (-1162)
Shale & Lime	3883	3975	B/KC	4298' (-1228)
Shale	3975	4098	Marmaton	4330' (-1260)
Shale & Lime	4098	4180	Johnson	4556' (-1486)
Lime & Shale	4180	4233	Upper Chero.	4480' (-1410)
Lime	4233	4650	Lower Chero.	4514' (-1444)
Rotary Total Depth		4650	<u>ELEC. LOG TOPS:</u>	
			Anhydrite	2563' (+ 507)
			B/Anhyd.	2588' (+ 482)
			Heebner	3974' (- 904)
			Toronto	4000' (- 930)
			Lansing	4021' (- 951)
			Stark Sh.	4238' (-1168)
			B/KC	4304' (-1234)
			Marmaton	4330' (-1260)
			Pawnee	4437' (-1367)
			Lower Chert	4518' (-1448)
			Johnson	4562' (-1492)
			Miss.	4613' (-1543)
			DTD	4650'
			LTD	4656'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF Kansas, COUNTY OF Sedgwick SS,


Jack L. Partridge OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS Vice President FOR Abercrombie Drilling, Inc.
 OPERATOR OF THE MOORE 'C' LEASE, AND IS DULY AUTHORIZED TO MAKE THIS
 AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS
 BEEN COMPLETED AS OF THE 21st DAY OF November 1981, AND THAT ALL
 INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(s) Jack L. Partridge
 Jack L. Partridge, Vice President

SUBSCRIBED AND SWORN TO BEFORE ME THIS 8th DAY OF December 1981

Elizabeth G. Terry
 NOTARY PUBLIC
 Elizabeth G. Terry


MY COMMISSION EXPIRES: 7-13-85