

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-135-22,766-00-00

LEASE NAME D. D. Johnson

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER 1

SPOT LOCATION E<sup>1</sup>/<sub>2</sub> E<sup>1</sup>/<sub>2</sub> SE

LEASE OPERATOR Bentley Oil & Gas Company

SEC. 31 TWP. 18 RGE. 25 (E) OR (W)

ADDRESS P. O. Box 5012, Wichita Falls, Texas 76307

COUNTY Ness  
(Drilling)

DATE WELL COMPLETED 3-18-85\*

PHONE #(817) 723-0897 OPERATORS LICENSE NO. 9310

PLUGGING COMMENCED 3-30-85

CHARACTER OF WELL D&A  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMPLETED 3-30-85

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? \_\_\_\_\_

IS ACC-1 FILED? yes IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION none DEPTH TO TOP \_\_\_\_\_ BOTTOM T.D. 4563'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS \_\_\_\_\_ CASING RECORD \_\_\_\_\_

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	724	8-5/8		

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Plugged: 3 sks cotton seed hulls, 15 sks gel, 100 sks 60/40 Poz cement w/2% gel and 3% CaCl, 5 sks gel, 1 sk cotton seed hulls, 8-5/8" rubber plug, 50 sks 60/40 poz cement w/2% gel and 3% Cacl

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Richardson Engineering & Management Co. LICENSE No. \_\_\_\_\_  
ADDRESS 2907 Lakeshore Drive Augusta, KS 67010

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Texas COUNTY OF Wichita SS. APR 22 1985

Cindy P. Miller (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Cindy P. Miller  
(ADDRESS) P. O. Box 5012  
Wichita Falls, Texas 76307

SUBSCRIBED AND SWORN TO BEFORE ME THIS 15 DAY OF April, 1985

Betty Mitchell  
NOTARY PUBLIC

MY COMMISSION EXPIRES: \_\_\_\_\_



BETTY MITCHELL  
Notary Public, State of Texas  
My Comm. Expires April 14, 1986

FORM CP-4  
REVISED 06-83

\* Completion was attempted, but was unsuccessful

WELL LOG

15-135-22766-00-00

Company: Bentley Oil & Gas Company

Sec: 31- T. 18S R. 25W

Farm: D. D. Johnson No. 1


Loc. 1450' NSE Cor./330' WSE Cor.

Total Depth: 4563 RTD

County: Ness, Kansas

Comm. 3-7-85

Comp. 3-17-85



Elevation:

Production: 4 1/2 set at 4562'

Contractor: DaMac Drilling Inc.

Casing: 8 5/8 set at 724'


Figures Indicate Bottoms of Formations

Shale, Rock	0	85
Shale	85	726
Shale, Redbed	726	1070
Shale	1070	1694
Anhydrite, Shale	1694	1726
Shale, Lime	1726	3977
Shale, Lime, Pyrite	3977	4089
Lime, Shale	4089	4420
Lime	4420	4563

State of Kansas  
County of Barton } KS

I, Bonnie Sarff of DaMac Drilling Inc.  
upon oath state the above and foregoing is true and correct copy of the log of the  
D.D. Johnson #1 well.

Bonnie Sarff



Subscribed and sworn to before me this 17th day of March 19 85.  
My Comm. Expires: May 9, 1987 Carmel Drehle

RECEIVED  
STATE CORPORATION COMMISSION

APR 22 1985  
04-22-1985  
CONSERVATION DIVISION  
Wichita, Kansas