

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-135-24198-0000

LEASE NAME Spruill

WELL NUMBER 1

2,310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 34 TWP. 18 RGE. 25 CORNER (W)

COUNTY Ness

Date Well Completed 10-22-02

Plugging Commenced 10-22-02

Plugging Completed 10-22-02

RECEIVED
10-30-2002
OCT 30 2002

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Carmen Schmitt, Inc.

ADDRESS PO Box 47, Great Bend, KS 67530

PHONE# (620) 793-5100 OPERATORS LICENSE NO. 6,569

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-21-02 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.O. 4,454'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	206'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each so
Push plug to 1,710', pump 50 sax cement on plug thru drill pipe; push plug to 1,050', pump 80 sax cement on plug thru drill pipe; push plug to 500', pump 40 sax cement on plug thru drill pipe; push plug to 230', pump 40 sax cement on plug thru drill pipe; push plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carmen Schmitt, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 28th day of October, 2002

Leuch Phillips
Notary Public

My Commission Expires: _____

NOTARY PUBLIC
STATE OF KANSAS
My Commission Expires 5-16-03




Shields

15-135-24198-00-00
Russell, Kansas

WELL LOG

Operator: CARMEN SCHMITT, INC.
 Well: SPRUILL #1
 Commenced: October 14, 2002
 Completed: October 22, 2002
 Contractor: Shields Drilling Co.

Well Description: NE NE SE
 Sec. 34-18S-25W
 Ness Co., KS



CASING RECORD

Size	Run	Pulled
8 5/8"	206'	Cmtd. w/150 sax

Elevation:
 Treatment: 2,407' KB
 Production: D & A
 Tops:

RECEIVED
 10-30-2002
 OCT 30 2002
 KCC WICHITA

..... Figures Indicate Bottom of Formations

Sand & shale	1,680'	
Anhydrite	1,715'	
Shale & sand	2,493'	
Shale	3,813'	
Shale & lime	4,130'	
Lime	4,254'	
Lime & shale	4,343'	
Lime	4,420'	
Mississippian	4,454'	RTD

Notes