

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-135-24143-0000

LEASE NAME Miner

WELL NUMBER 1-35

3,580 Ft. from S Section Line

165 Ft. from ^W Section Line

SEC. 35 TWP. 18 RGE. 25 (X) or (Y)

COUNTY Ness

Date Well Completed 9-3-01

Plugging Commenced 9-3-01

Plugging Completed 9-4-01

RECEIVED
09-12-2001
SEP 12 2001

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Carmen Schmitt, Inc.

ADDRESS PO Box 47, Great Bend, KS 67530

PHONE (620) 793-5100 OPERATORS LICENSE NO. 6,569

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-3-01 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4,453

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	211'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each so
Push plug to 1,720', pump 50 sax cement on plug thru drill pipe; push plug to 950', pump 80 sax cement on plug thru drill pipe; push plug to 500', pump 40 sax cement on plug thru drill pipe; push plug to 240', pump 40 sax cement on plug thru drill pipe; push plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carmen Schmitt, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor
(Employee of ~~Operator~~) ~~xxxxxx~~
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 11th day of September, 2001

Lucretia Phillips
Notary Public

My Commission Expires: 5-26-03



Shields


15-135-24143-00-00

Russell, Kansas

WELL LOG

Operator: Carmen Schmitt, Inc.
Well: Miner #1-35
Commenced: August 25, 2001
Completed: September 4, 2001
Contractor: Shields Drilling Co.

Well Description: 165' W, 50'S of NW SW NW
Sec. 35-18S-25W
Ness County, Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	211'	Cmtd. w/150 sax

Elevation: 2,411' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand & shale	1,685'
Anhydrite	1,720'
Shale & sand	1,818'
Shale	3,882'
Lime	4,453' RTD

RECEIVED

SEP 12 2001

KCC WICHITA

09-12-2001

Notes