


STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

R 15-135-00612-00-00
 WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

NESS

County. Sec. 19 Twp. 18S Rge. 25W (E) (W)

Location as "NE/CNW&SW¼" or footage from lines C NE SE
 Lease Owner HELMERICH & PAYNE, INC.
 Lease Name TENNY Well No. 1
 Office Address First National Building, Tulsa 3, Oklahoma
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed January 20, 19 62
 Application for plugging filed January 21, 19 62
 Application for plugging approved January 21, 19 62
 Plugging commenced January 22, 19 62
 Plugging completed January 22, 19 62
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, 805 Main, Victoria, Kansas
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4480 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Soil, Sand & Clay	Surface Csg.	-0-	337'	8-5/8"	337'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: Hole filled with mud 4480' to 550'; 20 sx. cement through drill pipe, plug, 1/4 sk. hulls. 20 sx. cement at 180', plug, 1/4 sk. hulls & 10 sx. cement at 40' by Halliburton.

01-24-1962

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
 Address 208 Petroleum Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.
C. T. HONAKER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DRIG. SUPT.

Box 232, Russell, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 19 62.

Terry L. Ditt
 Notary Public

Mv commission expires 10-17-63



15-135-00612-00

HELMERICH & PAYNE, INC. - Operator

SIERRA PETROLEUM CO., INC. - Contr.

TENNY #1
C NE SE
Sec. 19-18S-25W
Ness County, Kansas

T. D.: 4480'
Elev.: 2499' K.B.

Commenced: 1-9-62
Completed: 1-20-62

Casing:
8-5/8" Set at 337'

Cement:
with 175 sx. cement

FORMATION	DEPTH
Surface Soil, sand & clay	298
Shale	695
Shale & Red Bed	1160
Anhydrite	1180
Shale & Sand	1510
Shale	1780
Shale & Lime	2770
Lime	3195
Lime & Shale	3425
Lime	3665
Lime & Shale	3845
Lime	4345
Lime & Shale	4380
Lime	4424
Lime & Shale	4480

01-24-1962

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C.T. Henaker

Subscribed and sworn to before me this 23rd day of January, 1962.

Leroy Ditty
Notary Public

My commission expires: 10-17-63