


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County, Sec. 24 Twp. 18 Rge. 25 E/W  
Location as "NE/CNW/SW" or footage from lines  
C NE SW  
Lease Owner A. Scott Ritchie  
Lease Name Anspaugh #1 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 6/30/77 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 7/ 5/77 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_  
depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4390  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	289	none
				4 1/2"	4379	3740'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded to 4340' and ran 3 sacks cement. Loaded oil string with water, shot pipe at 3890', 3730', pulled 105 joints. Plugged well with 20 sacks gel, 70 sacks cement, 8 sacks gel, plug and 70 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 08 1977  
07-08-1977  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 77

NOTARY PUBLIC  
MARGARET MELCHER  
Rice County, Ks.  
My Comm. Exp. Feb. 15, 1979

Margaret Melcher  
Notary Public.

My commission expires \_\_\_\_\_

15-135-21271-00-00

D R I L L E R S   L O G

Anspaugh #1

CASING RECORD: 285½' used 8-5/8" 23# surface casing	COMPANY:     A. Scott Ritchie	DESCRIPTION:   C/NE SW Section 24-18S-25W Ness County, Kansas
	CONTRACTOR:   Strata Drilling Company	
	COMMENCED:    January 15, 1977	ELEVATION:    2367' GL
TOTAL DEPTH: 4390'	COMPLETED:   January 24, 1977	

<u>FORMATION</u>	<u>TO</u>	<u>FROM</u>	<u>REMARKS</u>
Surface rock and shale	0	300	Ran 285½' used 8-5/8" 23# casing; set and cemented @ 289' with 185 sacks common cement, 2% gel, 3% C.C.; cement circulated. Plug down 9:30 a.m., January 16, 1977.
Shale	300	1655	
Anhydrite	1655	1692	
Lime and Shale	1692	3800	
Lime	3800	3970	
Lime and Shale	3970	4370	
Dolomite Limestone	4370	4390	Ran two drill stem tests.
			Ran 122 jts. new 4½" casing; set @ 4379' with 85 sacks 60-40 pozmix, 2% gel, 18% salt. Plug down @ 7:20 a.m., January 24, 1977.

ROTARY DEPTH: 4390'

06-22-1977

STATE OF KANSAS )  
                          ) ss  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
 \_\_\_\_\_  
 Kenneth J. Link, President

Subscribed and sworn to before me this 8th day of February, 1977.  
My appointment expires: November 30, 1979.

*Joy Selves*  
 \_\_\_\_\_  
 Joy Selves, Notary Public

