

15-135-22666-00-00

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - RUPP #1

Located: C SE NW NW, Section 24-18S-25W, Ness County,
Kansas

OWNER: Walter Oil and Gas Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 14, 1984
COMPLETED: September 22, 1984

TOTAL DEPTH: 4429'

LOG

CASING RECORD

0 - 268 Surface Soil, Sand
and Shale

268 - 1708 Shale and Lime

1708 - 1723 Anhydrite

1723 - 4410 Lime and Shale

4410 - 4416 Lime

4416 - 4429 Mississippi

Ran 6 joints 8 5/8" casing. 253.64'
pipe set at 266' K.B. Cemented with
175 sacks 60/40 Pozmix, 2% gel and
3% cc. Plug down at 4:15 PM, 9-14-84,
by Howco.

Plugged.

Deviation Surveys:

1° at 1866'
3/4° at 4416'
3/4° at 4429'

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1984
CONSERVATION DIVISION
Wichita, Kansas

10-25-1984